

Figure N90-10 Test Sequence

ENGINE PREPARATION: PRETEST MEASUREMENTS,
PERFORMANCE CHECKS AND CALIBRATIONS

START

GENERATE MAXIMUM TORQUE CURVE

PRACTICE CYCLE RUNS

SAMPLING SYSTEM PRECONDITIONING

COLD SOAK OR COOL DOWN

COLD START EXHAUST EMISSION TEST

20 MINUTE HOT SOAK

HOT START EXHAUST EMISSION TEST

END